



1. WORK SHALL BE PERFORMED IN ACCORDANCE TO STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
2. SILT FENCE AND EROSION CONTROL FEATURES MUST BE INSTALLED PRIOR TO SOIL DISTURBANCE.
3. SILT FENCE OR OTHER APPROVED BMP MUST BE PLACED TO INTERCEPT RUNOFF FROM TURBINE AREAS, COLLECTION SYSTEM, TRANSMISSION LINES, SUBSTATIONS AND DISTURBED AREAS THAT ARE LOCATED WITHIN 200 FEET OF ANY SURFACE WATER.
4. EROSION LOGS OR CERTIFIED WEED FREE STRAW BALES MAY BE USED AS ALTERNATIVES TO SILT FENCE.
5. REVEGETATION AND RESTORATION ACTIVITIES MUST BE CONDUCTED IN ACCORDANCE WITH THE SITE SPECIFIC RESTORATION AND WEED MANAGEMENT PLAN (ATTACHMENT H OF SWPPP).
6. DITCH PROTECTION: SILT FENCE, CHECK DAMS OR EROSION LOGS SHALL BE IMPLEMENTED ALONG ROADS AND ADJACENT TO SURFACE WATER AND DRY WASH CROSSINGS AS NECESSARY TO PREVENT EROSION IN DITCHES AND TRANSFER OF SEDIMENT.
7. REMOVE SOIL TRACKED ONTO IMPERVIOUS ROADS DAILY.
8. FOR PIPES GREATER THAN OR EQUAL TO 30", USE 1.5".
9. THE FABRIC SHOULD COVER THE AREA OF THE RIPRAP AND EXTEND UNDER THE CULVERT APRON 3 FEET.



RIPRAP QUANTITIES AT CULVERT OUTLETS

DIA. OF PIPE (INCHES)	L (FEET)	RIPRAP (CU. YD.)
18	10	9.4
24	12	13.0
30	14	17.1
36	16	21.8
42	18	27.0

5 **DETAIL: RIPRAP**
— NO SCALE



09/30/11 FOR CONSTRUCTION

[illegible]

Images in Drawing - M:\Design\34331007.04\Drawings\Client Logo.jpg K:\Design\34331006.01\jxb_signature.tif K:\Design\34331006.01\JXB-BISON 3 IFC.tif